

REMOVAL OF ADVANCED TRAFFIC MANAGEMENT SYSTEM EQUIPMENT - Item No.

Special Provision No. 682F22

November 2016

Amendment to OPSS 610, November 2016

610.07 CONSTRUCTION

Section 610.07 of OPSS 610 is amended by the addition of the following subsection:

610.07.13 Advanced Traffic Management System Equipment

A detailed equipment removal plan with detailed schedule and procedures shall be submitted for review and approval to the Contract Administrator 2 weeks prior to commencing any removal work.

Prior to removal operations, all equipment to be salvaged shall be inspected and tested. The Contract Administrator will witness all tests and inspections. Twenty-four hours advance notice shall be provided to the Contract Administrator prior to commencing any removal work.

The following test and/or inspections shall be performed for equipment to be salvaged under this Contract:

[* Designer Fill-in - See Notes to Designer]

Equipment	Test / Inspection Details

The following equipment shall be removed and salvaged for delivery/storage as indicated:

[** Designer Fill-in - See Notes to Designer]

Description	Quantity	Delivery / Storage Location

The following equipment shall be removed and salvaged for re-installation under this Contract. A temporary storage location with regulated environmental controls to meet the manufacturers storage requirements shall be utilized when equipment cannot be re-installed and re-energized during the same working day as removal:

[*** Designer Fill-in - See Notes to Designer]

Description	Quantity	Temporary Storage Location

The above equipment shall be delivered to and from the Working Area if temporary storage is required.

All remaining equipment identified for removal shall become the property of the Contractor and shall be managed as specified in the Contract Documents.

Where the Owner's premises are required for delivery and/or storage, 72 hours notice shall be provided to the Contract Administrator prior to delivery and/or pickup. The delivery and/or pickup from Owner's premises shall be made between 7:00 am and 3:00 pm Monday through Friday.

610.10 BASIS OF PAYMENT

Section 610.10 of OPSS 610 is amended by the addition of the following subsection:

610.10.02 Removal of Advanced Traffic Management System Equipment - Item

Payment at the Contract price for the above tender item shall be full compensation for all labour, Equipment, and Material to do the work.