

**AMENDMENT TO OPSS 617, NOVEMBER 2013**

---

Special Provision No. 106S16

March 2018

---

**617.03                      DEFINITIONS**

Section 617.03 of OPSS 617 is deleted in its entirety.

**617.07                      CONSTRUCTION**

**617.07.10                Quality Control**

Subsection 617.07.10 of OPSS 617 is deleted in its entirety and replaced with the following:

**617.07.10.01            Pre-Installation Testing and Inspection**

Luminaires, brackets, socket setting, refractor type, and ballast type shall be inspected to ensure they meet the requirements of the Contract Documents.

A Request to Proceed shall be submitted to the Contract Administrator after completion of the pre-installation testing and inspection.

The next operation after the completion of the pre-installation testing and inspection shall not proceed until a Notice to Proceed has been received from the Contract Administrator.

**617.07.10.02            Proof of Performance Testing and Inspection**

Luminaires shall be tested and inspected to ensure that they are levelled correctly and according to the Contract Documents. All luminaires shall have a minimum burning-in period of 100 nighttime hours prior to acceptance of the work by the Contract Administrator. All luminaire shielding shall be installed prior to the start of the burn-in period.

All tests required on the wiring system shall be according to OPSS 604.

A Request to Proceed shall be submitted to the Contract Administrator after completion of the proof of performance testing and inspection.

The next operation after the completion of the proof of performance testing and inspection shall not proceed until a Notice to Proceed has been received from the Contract Administrator.