

SMALL SIGNS, CONCRETE MEDIAN BARRIER MOUNTED WITH WOODEN POST, NEW - Item No.

SMALL SIGNS, CONCRETE MEDIAN BARRIER MOUNTED WITH METAL POST, NEW - Item No.

Special Provision No.703S02

May 2019

Amendment to OPSS 703, November 2014

Small Signs on Concrete Median Barriers

703.03 DEFINITIONS

Section 703.03 of OPSS 703 is amended by the addition of the following definition:

Metal Components means components including slide assembly, collar assembly, and pipe post.

Section 703.03 of OPSS 703 is further amended by deleting the definitions for **Small Sign Assembly** and **Sign Support System** and replacing them with the following:

Small Sign Assembly means one or more signs mounted on a sign support system with specified sign hardware having a total sign or sign board area not greater than 3.6 m² for ground mounted signs and 1.35 m² for signs mounted on concrete median barrier.

Sign Support System means a wooden or steel post of specified dimensions, hardware, and material erected vertically into the ground or on top of concrete median barrier for mounting signs at a specified height above the roadway.

703.05 MATERIALS

703.05.02 Wooden Posts

703.05.02.03 Marking of Wood for Identification of Grade and Species

Clause 703.05.02.03 of OPSS 703 is amended by deleting the last sentence and replacing it with the following:

The stamp shall be visible after installation and located at least 1.5 m above the finished grade.

703.05.02.04 Marking of Wood for Identification of Preservative Treatment

Clause 703.05.02.04 of OPSS 703 is amended by deleting the last sentence and replacing it with the following:

The wood preservative stamp shall be visible after installation and located at least 1.5 m above the finished grade.

703.05.03 Metal Posts

Subsection 703.05.03 of OPSS 703 is deleted in its entirety and replaced with the following:

703.05.03.01 Metal Components and Hardware

All metal components and hardware shall be as specified in the Contract Documents.

All metal components after fabrication shall be filed smooth and surface free of foreign materials before being hot dip galvanized according to ASTM A 123.

All sign hardware except setscrews shall be hot dip galvanized according to ASTM A 153. All setscrews shall be stainless steel.

703.07 CONSTRUCTION

Section 703.07 of OPSS 703 is amended by the addition of the following subsection:

703.07.07 Installation on Concrete Median Barrier

All sign support systems on top of concrete median barrier shall be installed as specified in the Contract Documents.

The top of all concrete barriers shall be ground smooth to provide a uniform flat surface over the length of the slide assembly and steel base prior to installation of anchors.

703.09 MEASUREMENT FOR PAYMENT

703.09.01 Actual Measurement

Clause 703.09.01.01 of OPSS 703 is amended by the addition of the following to the title:

**703.09.01.01 Small Signs, Concrete Median Barrier Mounted with Wooden Post, New
Small Signs, Concrete Median Barrier Mounted with Metal Post, New**

703.10 BASIS OF PAYMENT

Subsection 703.10.01 is amended by the addition of the following to the title:

**703.10.01 Small Signs, Concrete Median Barrier Mounted with Wooden Post, New - Item
Small Signs, Concrete Median Barrier Mounted with Metal Post, New - Item**